

Royal | PROJECTS  
Vriesco

BIRDSEYE F.R. NATURAL

## QUALITY BENEFITS

Acoustic performances | Flame retardant | Rich colors

## ENVIRONMENTAL BENEFITS

Made with recycled PET | Fully recyclable | No use of environmentally harmful dyes | Complies with REACH and BSCI regulation



**STANDARD  
100**  
2105107  
Centexbel



## DESCRIPTION






Birdseye is a high quality acoustical curtain fabric with a sustainable footprint. Birdseye has a beautiful graphic blended woven structure on the front and a fleece look-a-like back. Thanks to the rich structure the deep colors stand out very well. To produce Birdseye, used plastic PET bottles are collected and transformed into reusable polyester yarns. This process is significantly more energy-efficient than for virgin polyester and reduces the use of natural resources. Per square meter, Birdseye contains no less than 9 used plastic bottles. The fabric has a wonderfully soft touch and is available in 10 inspiring colors.



## AVAILABLE COLORS



## SPECIFICATIONS

Height/width	140 cm
Colors	10 colors
Composition	100% polyester (30% recycled)
Weight gr/m1	473
Weight gr/m2	338
Pattern height/width	-
Shrinkage tolerance	2% height, 0% width
Light fastness ISO 105-B02 (Class 1-8)	5
Cleaning	    
Suitable for Roman blinds	Yes - price range D
Flame Retardant	M1 (NF P 92 503-507) , EN 13773 Class 4 IMO 2010 FTP Code Annex 1, Part 7
Recycled %	30%
Absorption EN ISO 354	$\alpha_w=0,75$
Black-out	No