



Royal | PROJECTS
Vriesco

FURAN F.R. MILK

QUALITY BENEFITS

Super room high – Flame retardant – Natural look – Good lightfastness

ENVIRONMENTAL BENEFITS

Made with recycled PET – Fully recyclable – No use of environmentally harmful dyes – Complies with REACH and BSCI regulation



**STANDARD
100**
2105107
Centexbel

FURAN F.R.

DESCRIPTION

Furan is a naturally looking transparent curtain fabric with a sustainable footprint. The open linen-look-a-like structure is created with a mixture of yarns of uneven thickness and in several different color depths. Furan is fused with a technologically advanced material. To produce Furan, used plastic PET bottles are collected and transformed into reusable polyester filaments. This process is significantly more energy-efficient than for virgin polyester and reduces the use of natural resources. Furan is available in a wide range of natural and deep colors. The palette contains 19 inspiring colors.



AVAILABLE COLORS



SPECIFICATIONS

Height/width	315 cm
Colors	19 colors
Composition	100% polyester (43% recycled)
Weight gr/m1	318
Weight gr/m2	101
Pattern height/width	-
Shrinkage tolerance	0% height, 1% width
Light fastness ISO 105-B02 (Class 1-8)	6
Cleaning	
Suitable for Roman blinds	Yes - Price range D
Flame Retardant	M1 (NF P 92 503-507), EN 13773 Class 1, B1 (DIN 4102, part 1)
Recycled %	43%
Weighted drapery cord	Yes